



Revision Dates	
1	08.15.24
2	01.01.25
SHEET TITLE	
Door-Windows Schedule & Notes	
Check By	08.24.26
Drawn By	FRANCIS N.
Scale	As indicated
Job Number	081623
Sheet Number	

ADU DOOR SCHEDULE									
Mark	Count	Description	Width	Height	Sill Height	Head Height	Thickness	Level	Comments
101	1		3' - 0"	7' - 0"	0' - 0"	7' - 0"	0' - 2"	1st Floor Level	ADU
102	1		2' - 6"	6' - 8"	0' - 0"	6' - 8"	0' - 2"	1st Floor Level	ADU
103	1		2' - 6"	6' - 8"	0' - 0"	6' - 8"	0' - 2"	1st Floor Level	ADU
104	1		5' - 8"	6' - 8"	0' - 0"	6' - 8"	0' - 2"	1st Floor Level	ADU
105	1		2' - 6"	6' - 8"	0' - 0"	6' - 8"	0' - 2"	1st Floor Level	ADU
106	1		5' - 8"	6' - 8"	0' - 0"	6' - 8"	0' - 2"	1st Floor Level	ADU
107	1		1' - 6"	6' - 8"	0' - 0"	6' - 8"	0' - 2"	1st Floor Level	ADU
108	1		1' - 6"	6' - 8"	0' - 0"	6' - 8"	0' - 2"	1st Floor Level	ADU
201	1		3' - 0"	7' - 0"	0' - 0"	7' - 0"	0' - 2"	2nd Floor Plan	ADU
202	1		1' - 3"	6' - 1"	0' - 0"	6' - 1"	0' - 1"	2nd Floor Plan	ADU
203	1		1' - 3"	6' - 1"	0' - 0"	6' - 1"	0' - 1"	2nd Floor Plan	ADU
204	1		2' - 6"	6' - 8"	0' - 0"	6' - 8"	0' - 2"	2nd Floor Plan	ADU
205	1		2' - 6"	6' - 8"	0' - 0"	6' - 8"	0' - 2"	2nd Floor Plan	ADU
206	1		5' - 8"	6' - 8"	0' - 0"	6' - 8"	0' - 2"	2nd Floor Plan	ADU
207	1		2' - 6"	6' - 8"	0' - 0"	6' - 8"	0' - 2"	2nd Floor Plan	ADU
208	1		5' - 8"	6' - 8"	0' - 0"	6' - 8"	0' - 2"	2nd Floor Plan	ADU
209	1		1' - 6"	6' - 8"	0' - 0"	6' - 8"	0' - 2"	2nd Floor Plan	ADU
210	1		1' - 6"	6' - 8"	0' - 0"	6' - 8"	0' - 2"	2nd Floor Plan	ADU

ADU WINDOW SCHEDULE									
Mark	Count	Description	Level	Height	Width	Sill Height	Manufacturer	Model	Comments
01	1		1st Floor Level	5' - 0"	4' - 0"	2' - 7 1/2"			ADU
02	1	Gliding	1st Floor Level	4' - 0"	4' - 0"	3' - 0"			ADU
03	1	Gliding	1st Floor Level	1' - 2"	3' - 0"	5' - 0"			ADU
04	1	Gliding	1st Floor Level	4' - 0"	4' - 0"	3' - 0"			ADU
05	1	Gliding	1st Floor Level	4' - 0"	4' - 0"	3' - 0"			ADU
06	1		1st Floor Level	4' - 0"	2' - 0"	3' - 0"			ADU
07	1		1st Floor Level	4' - 0"	2' - 0"	3' - 0"			ADU
08	1		1st Floor Level	5' - 0"	4' - 0"	2' - 7 1/2"			ADU
21	1		2nd Floor Plan	5' - 0"	4' - 0"	2' - 7 1/2"			ADU
22	1	Gliding	2nd Floor Plan	4' - 0"	4' - 0"	3' - 0"			ADU
23	1	Gliding	2nd Floor Plan	1' - 2"	3' - 0"	5' - 0"			ADU
24	1	Gliding	2nd Floor Plan	4' - 0"	4' - 0"	3' - 0"			ADU
25	1	Gliding	2nd Floor Plan	4' - 0"	4' - 0"	3' - 0"			ADU
26	1		2nd Floor Plan	4' - 0"	2' - 0"	3' - 0"			ADU
27	1		2nd Floor Plan	4' - 0"	2' - 0"	3' - 0"			ADU
28	1		2nd Floor Plan	5' - 0"	4' - 0"	2' - 7 1/2"			ADU

GENERAL NOTES

- THE BUILDER IS TO PROVIDE AN OPERATION MANUAL (CONTAINING INFORMATION FOR MAINTAINING APPLIANCES, ETC.) FOR THE OWNER AT THE TIME OF FINAL INSPECTION. CGC 4.410.1.
- DURING CONSTRUCTION, ENDS OF DUCT OPENINGS ARE TO BE SEALED, AND MECHANICAL EQUIPMENT IS TO BE COVERED. CGC 4.504.1
- THE GAS FIREPLACE(S) SHALL BE DIRECT VENT. WOODSTOVE OR PELLET STOVES MUST BE US EPA PHASE II RATED APPLIANCES. CGC 4.503.1
- VOC'S MUST COMPLY WITH THE LIMITATIONS LISTED IN SECTION 4.504.3 AND TABLES 4.504.1, 4.504.2, 4.504.3 AND 4.504.5 FOR: ADHESIVES, PAINTS AND COATINGS, CARPET AND COMPOSITION WOOD PRODUCTS. CGC 4.504.2.
- INTERIOR MOISTURE CONTROL AT SLAB ON GRADE FLOORS SHALL BE PROVIDED BY THE SOIL ENGINEER RESPONSIBLE FOR THE PROJECT SOIL REPORT PER CGC SECTION 5.505.2.1, ITEM 3. IF A SOIL ENGINEER HAS NOT PREPARED A SOIL REPORT FOR THIS PROJECT, THE FOLLOWING IS REQUIRED: A 4" THICK BASE 1/2" OR LARGER CLEAN AGGREGATE SHALL BE PROVIDED WITH A VAPOR BARRIER IN DIRECT CONTACT WITH CONCRETE, WITH A CONCRETE MIX DESIGN WHICH WILL ADDRESS BLEEDING, SHRINKAGE AND CURLING SHALL BE USED.
- THE MOISTURE CONTENT OF WOOD SHALL NOT EXCEED 19% BEFORE IT IS ENCLOSED IN CONSTRUCTION. THE MOISTURE CONTENT NEEDS TO BE CERTIFIED BY ONE OF 3 METHODS SPECIFIED. BUILDING MATERIALS WITH VISIBLE SIGNS OF WATER DAMAGE SHOULD NOT BE USED IN CONSTRUCTION. THE MOISTURE CONTENT MUST BE DETERMINED BY THE CONTRACTOR BY ONE OF THE METHODS LISTED IN CGC SECTION 4.505.3.
- BATHROOM FANS SHALL BE ENERGY STAR RATED, VENTED DIRECTLY TO THE OUTSIDE AND CONTROLLED BY A HUMIDISTAT. CGC 4.506.1.
- IF PROVIDED, WHOLE HOUSE EXHAUST FANS SHALL HAVE INSULATED COVERS OR LOUVERS WHICH CLOSE WHEN THE FAN IS OFF. THE COVERS OR LOUVERS SHALL HAVE MINIMUM R4.2 INSULATION. CGC 5.507.1.
- HEATING AND AC SHALL BE SIZED AND SELECTED BY ACCA MANUAL J OR ASHRAE HANDBOOK OR EQUIVALENT. THE DUCT SIZING SHALL BE SIZED IN ACCORDANCE WITH ONE OF THE ACCA METHODS LISTED IN CGC SECTION 4.507.2.
- PRIOR TO FINAL APPROVAL OF THE BUILDING THE LICENSED CONTRACTOR, ARCHITECT OR ENGINEER IN RESPONSIBLE CHARGE OF THE OVERALL CONSTRUCTION MUST COMPLETE AND SIGN THE GREEN BUILDING STANDARDS CERTIFICATION
- FORM AND GIVEN TO THE BUILDING DEPARTMENT OFFICIAL TO BE FILED WITH THE APPROVED PLANS.
- WHEN A SHOWER IS PROVIDED WITH MULTIPLE SHOWER HEADS, THE SUM OF FLOW TO ALL THE HEADS SHALL NOT EXCEED THE 20% REDUCED LIMIT, OR THE SHOWER SHALL BE DESIGNED SO THAT ONLY ONE HEAD IS ON AT A TIME. CGC 4.303.2.
- LANDSCAPE IRRIGATION WATER USE SHALL HAVE WEATHER BASED CONTROLLERS. CGC 4.304.1.
- AN AUTOMATIC RESIDENTIAL FIRE SPRINKLER SYSTEM SHALL BE INSTALLED IN ONE- AND TWO-FAMILY DWELLINGS.
- GARAGE SHALL BE SEPARATED FROM THE RESIDENCE AND ITS ATTIC AREA BY NOT LESS THAN 1/2" GYPSUM BOARD APPLIED TO THE GARAGE SIDE (AT WALLS). GARAGES BENEATH HABITABLE ROOMS SHALL BE SEPARATED BY NOT LESS THAN 5/8" TYPE X GYPSUM BOARD. SECTION 406.1.4. STRUCTURAL MEMBERS SUPPORTING A HORIZONTAL FIRE BARRIER MUST HAVE THE SAME FIRE-RESISTIVE RATING AS THE SEPARATION. SECTION 711.4.
- COMBUSTION AIR FOR FUEL BURNING WATER HEATERS WILL BE PROVIDED IN ACCORDANCE WITH THE PLUMBING CODE
- THE WALLS AND SOFFITS OF THE ENCLOSED USABLE SPACE UNDER INTERIOR STAIRS SHALL BE PROTECTED ON THE ENCLOSED SIDE WITH 1/2-INCH GYPSUM BOARD
- UNDER-FLOOR VENTILATION SHALL BE NOT LESS THAN 1/150 OF UNDER FLOOR AREA.
- THE WATER HEATER SHALL BE STRAPPED AS PER UPC SECTION 510.5 W/ 1 1/2" WIDE 16 GA. METAL STRAPS (ONE AT 1/3 FROM THE TOP AND ONE 1/3 FROM THE BOTTOM OF THE WATER HEATER).
- THE PRESSURE RELIEVE VALVE OF THE WATER HEATER SHALL DRAIN TO THE OUTSIDE OF THE BUILDING WITH THE END PIPE NOT MORE THAN 2' AND NOT LESS THAN 6" ABOVE THE GROUND PER UPC SECTION 608.5.
- PROVIDE A MIN. 22" X 30" ATTIC ACCESS
- PROVIDE 70" HIGH NON-ABSORBENT WALL ADJACENT TO SHOWER AND APPROVED SHATTER-RESISTANT MATERIALS FOR SHOWER.
- PROVIDE ULTRA FLUSH WATER CLOSETS FOR ALL NEW CONSTRUCTION. SHOWER HEADS AND TOILETS MUST BE ADAPTED FOR LOW WATER CONSUMPTION.

FLOOR PLAN GENERAL NOTE

1/4" = 1'-0"

MECHANICAL GENERAL NOTES:

- BUILDING IS TWO STORY.
- FURNISH ALL LABOR, MATERIALS, TOOLS, EQUIPMENT, FEES, PERMITS, CERTIFICATE OF INSPECTION, ETC., NECESSARY OR REASONABLY REQUIRED FOR THE COMPLETE INSTALLATION OF ALL AIR CONDITIONING WORK. THE WORK SHALL BE IN STRICT ACCORDANCE WITH THE ASHRAE GUIDE, AND ALL LOCAL AND STATE CODES, ORDINANCES AND REGULATIONS.
- COORDINATE ALL MECHANICAL WORK WITH ARCHITECT AND OTHER TRADES PRIOR TO WORK.
- ALL OUTSIDE AIR INTAKES SHALL BE MINIMUM 10 FEET FROM ANY EXHAUST OR PLUMBING VENTS - COORDINATE WITH PLUMBING CONTRACTOR.
- EXHAUST DUCTS MUST TERMINATE 10 FEET HORIZONTALLY FROM OR 3 FEET ABOVE ALL AIR INTAKES.

EQUIPMENT:

- MECHANICAL CONTRACTOR TO VERIFY AND COORDINATE AVAILABLE VOLTAGE WITH ELECTRICAL CONTRACTOR PRIOR TO ORDERING EQUIPMENT.
- ALL MECHANICAL EQUIPMENT LOCATIONS TO COMPLY WITH THE 2022 CMC.
- SET A/C UNITS TO OUTSIDE AIR QUANTITIES AS SPECIFIED ON FLOOR PLAN.
- ALL HVAC EQUIPMENT (A/C UNITS, EXHAUST FANS, ETC.) SHALL BE U.L. LISTED.
- ALL MOTORS SHALL BE INHERENTLY THERMALLY PROTECTED.
- CONTRACTOR SHALL MOUNT ALL MECHANICAL EQUIPMENT LEVEL IN CONFORMANCE WITH MANUFACTURER'S INSTRUCTIONS.
- PROVIDE ONE SET OF FARR 30-30 THROWAWAY FILTERS AND ONE SET OF FINAL FILTERS, FRAMES, MOUNTING HARDWARE AND ACCESSORIES. PROVIDE ONE SET OF THROWAWAY FILTERS FOR USE DURING THE CONSTRUCTION PERIOD. REMOVE THE FIRST SET OF THROWAWAY FILTERS AFTER THE CONSTRUCTION PERIOD AND INSTALL THE SECOND SET OF FINAL FILTERS (PRIOR TO BALANCING THE SYSTEM).

DUCT WORK:

- THE MAXIMUM LENGTH OF ANY FLEX DUCT SHALL NOT EXCEED 8 FEET.
- ALL SUPPLY AND RETURN DUCTS SHALL HAVE A MINIMUM OF R-6 INSULATION (R-8 IN UNCONDITIONED ATTIC) PER THE CALIFORNIA ENERGY CODE.
- ALL JOINTS, LONGITUDINAL AND TRANSVERSE SEAMS AND CONNECTIONS IN DUCTWORK SHALL BE SECURELY FASTENED AND SEALED WITH WELDS, GASKETS, MASTICS (ADHESIVES), MASTIC-PLUS-EMBEDDED-FABRIC SYSTEMS OR TAPES. TAPES AND MASTICS USED TO SEAL DUCTWORK SHALL BE LISTED AND LABELED IN ACCORDANCE WITH UL 181A AND SHALL BE MARKED 181A-P FOR PRESSURE SENSITIVE TAPE. TAPES AND MASTICS USED TO SEAL FLEXIBLE AIR DUCT AND FLEXIBLE CONNECTORS SHALL COMPLY WITH UL 181B AND SHALL BE MARKED 181B-FX FOR PRESSURE SENSITIVE TAPE OR 181M FOR MASTIC. DUCT CONNECTIONS TO FLANGES OF AIR DISTRIBUTION SYSTEM EQUIPMENT SHALL BE SEALED AND MECHANICALLY FASTENED. UNLISTED DUCT TAPE IS NOT PERMITTED AS SEALANT ON ANY METAL DUCTS.
- ALL DUCTS SHALL BE SUBSTANTIALLY SUPPORTED WITH HANGERS TO THE STRUCTURE. SHEET METAL SHALL BE IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: UP TO 12" WIDTH - 26 GAUGE STEEL; 13" TO 30" WIDTH - 24 GAUGE STEEL.
- ALL "FACTORY MADE" DUCT MUST BE CLASS "0" OR CLASS "1".
- ALTERNATE FOR SHEET METAL DUCTWORK, FOR AIR CONDITIONING SUPPLY AND RETURN: 1-1/2" THICK FIBERGLASS DUCTBOARD, WITH FOIL-SCRIM-KRAFT FIRE RESISTANT OUTER JACKET. MATERIAL SHALL COMPLY WITH UL-181, NFPA 90A AND 90B. CLOSURES SHALL BE MADE WITH THERMAL-ACTIVATED TAPE, OR CLOTH TAPE SET IN BRUSH-APPLIED ADHESIVE. DO NOT UTILIZE PRESSURE SENSITIVE TAPE.

OUTLETS:

- THE MECHANICAL CONTRACTOR SHALL COORDINATE EXACT DIFFUSER AND GRILLE LOCATIONS WITH ELECTRICAL CONTRACTOR AND ALL OTHER TRADES, AND ALSO COORDINATE SPACE AVAILABILITY FOR DUCTWORK ABOVE RECESSED LIGHTING TO AVOID RELOCATING DUCTWORK AT THE MECHANICAL CONTRACTOR'S EXPENSE.
- ALL AIR DISTRIBUTION DEVICES IN LAY-IN CEILINGS SHALL BE SUPPORTED IN COMPLIANCE WITH NFPA 90A AND THE 2022 CBC.

CONTROLS:

- THERMOSTATS SHALL BE 7-DAY PROGRAMMABLE, SET WITH FAN ON CONTINUOUSLY.

FIRE:

- APPROVED SMOKE DETECTOR DEVICES SHALL BE INSTALLED WITH ALL AIR MOVING SYSTEMS (EITHER INDEPENDENT OR COMBINED IN A COMMON PLENUM OR SERVING A COMMON ROOM) OVER 2000 CFM, LOCATED IN THE SUPPLY AIR DUCTWORK. DEVICES SHALL AUTOMATICALLY SHUT DOWN THE UNIT WHEN PARTICLES OF COMBUSTION ARE DETECTED WITHIN THE AIR STREAM, PER THE 2022 CMC.
- ALL SMOKE DETECTORS SHALL BE TESTED BY AN AABC OR NEBB CERTIFIED AIR BALANCE TECHNICIAN PER CITY OF SAN DIEGO REQUIREMENTS FOR SPECIAL INSPECTIONS IN COMPLIANCE WITH THE 2022 C.M.C. THE MECHANICAL CONTRACTOR SHALL INCLUDE ALL FEES FOR THESE TESTS AND INSPECTIONS IN HIS BID.
- IF THERE IS A FIRE ALARM SYSTEM, ALL SMOKE DETECTORS SHALL BE MONITORED BY THAT SYSTEM.

PIPING:

- HANGERS AND SUPPORTS: CLEVIS HANGERS, ADJUSTABLE HEIGHT, MAXIMUM 10' O.C., 3/8" ROD UP TO 5" PIPES, 5/8" ROD FOR 6" AND LARGER. WHERE EXTRA HANGER SUPPORTS ARE REQUIRED THEY SHALL BE PROVIDED BY THE CONTRACTOR. TRAPEZE HANGERS WITH ROLLERS MAY BE USED FOR MULTIPLE LINES OR WHERE SPACE IS LIMITED.

INSULATION:

- ALL INSULATION, MATERIAL, COVERINGS, ADHESIVES, VAPOR-BARRIERS AND TAPES SHALL CONFORM TO NFPA 90A, FLAME SPREAD CLASSIFICATION NOT TO EXCEED 25 AND SMOKE DEVELOPMENT NOT TO EXCEED 50.
- PROVIDE 1/2" LINER IN SUPPLY AND RETURN DUCTWORK OF AIR CONDITIONING SYSTEMS.
- INSULATE ALL SHEET METAL DUCTWORK FOR AIR CONDITIONING SYSTEM WITH 1 1/2" LB. DENSITY FIBERGLASS INSULATION. TAPES, JOINTS AND FITTINGS SHALL BE LABELED.

ADU MECH GENERAL NOTES

12" = 1'-0"

CALIFORNIA GREEN CODE STANDARDS

PER 2022 GREEN CODE SEC 4.303.3 PLUMBING FIXTURES (WATER CLOSETS AND URINALS) AND FITTINGS (FAUCET AND SHOWER HEADS) SHALL MEET THE STANDARDS REFERENCED IN TABLE 4.303.3 (REFER TO TABLE ON SHEET A04)

AUTOMATIC IRRIGATION SYSTEM CONTROLLERS FOR LANDSCAPING PROVIDED BY THE BUILDER AND INSTALLED AT THE TIME OF FINAL INSPECTION SHALL COMPLY WITH THE FOLLOWING:

1. CONTROLLERS SHALL BE WEATHER-OR SOIL MOISTURE-BASED CONTROLLERS THAT AUTOMATICALLY ADJUST IRRIGATION IN RESPONSE TO CHANGES IN PLANTS NEEDS AS WEATHER CONDITIONS CHANGE

2. WEATHER-BASED CONTROLLERS WITHOUT INTEGRAL RAIN SENSORS OR COMMUNICATION SYSTEMS THAT ACCOUNT FOR LOCAL RAINFALL SHALL HAVE A SEPARATE WIRED OR WIRELESS RAIN SENSOR WHICH CONNECTS OR COMMUNICATES WITH THE CONTROLLER(S). SOIL MOISTURE-BASED CONTROLLERS ARE NOT REQUIRED TO HAVE RAIN SENSOR INPUT.

PER 2013 GREEN CODE SEC 4.503.1 ANY INSTALLED GAS FIREPLACE SHALL BE A DIRECT-VENT SEALED-COMBUSTION TYPE. ANY INSTALLED WOODSTOVE OR PELLET STOVE SHALL COMPLY WITH U.S. EPA PHASE II EMISSION LIMITS WHERE APPLICABLE. WOODSTOVES, PELLET STOVES AND FIREPLACES SHALL ALSO COMPLY WITH APPLICABLE LOCAL ORDINANCES.

PER 2010 GREEN CODE SEC 4.506.1 MECHANICAL EXHAUST FANS WHICH EXHAUST DIRECTLY FROM BATHROOMS SHALL COMPLY WITH THE FOLLOWING:

1. FANS SHALL BE ENERGY STAR COMPLIANT AND BE DUCTED TO TERMINATE OUTSIDE THE BUILDING.

2. UNLESS FUNCTIONING AS A COMPONENT OF A WHOLE HOUSE VENTILATION SYSTEM, FANS MUST BE CONTROLLED BY A HUMIDISTAT WHICH SHALL BE READILY ACCESSIBLE. HUMIDISTAT CONTROLS SHALL BE CAPABLE OF ADJUSTMENT BETWEEN A RELATIVE HUMIDITY RANGE OF 50 TO 80 PERCENT

A SIGNED AFFIDAVIT FROM INSTALLER STATING METHOD USED FOR THE SELECTION OF HEATING AND AIR CONDITIONING EQUIPMENT AND THAT SUCH EQUIPMENT WAS INSTALLED IN ACCORDANCE TO THAT METHOD IS REQUIRED; THIS AFFIDAVIT SHALL BE PRESENTED TO THE BUILDING INSPECTOR BEFORE FINAL INSPECTION

1 ADU- GREEN CODE NOTES

1 1/2" = 1'-0"

2