STRUCTURAL MATERIAL SPECIFICATIONS

CONCRETE:

1. CEMENT SHALL BE PORTLAND CEMENT CONFORMING TO ASTM C150 - TYPE II (USE TYPE V CEMENT WITH APPROPRIATE WATER TO CEMENT RATIO PER SECTION 1904.3 OF THE UBC FOR SOILS WITH SEVERE OR VERY SEVERE SULFATE EXPOSURE)
2. MINIMUM 28-DAY ULTIMATE COMPRESSIVE STRENGTH 2,500 psi., U.N.O. CONTINUOUS INSPECTION BY A DEPUTY INSPECTION IS NOT REQUIRED.
3. AGGREGATES:

   LIGHTWEIGHT — ASTM C-330
   HARDROCK — ASTM C-33
4. CONCRETE COVERAGE OF REINFORCING STEEL:

   UNFORMED SURFACES CAST DIRECTLY AGAINST EARTH
   SLABS-ON-EARTH — AT C.L. SLAB
   ALL OTHER CONCRETE — 3 INCHES

   FORMED AND/OR FINISHED SURFACES EXPOSED TO EARTH OR WEATHER.
   #5 BAR AND SMALLER — 1-1/2 INCHES
   #6 BAR AND LARGER — 2 INCHES
5. FORMS AND SHORING SHALL REMAIN UNDISTURBED AS FOLLOWS:

   VERTICAL SURFACES — 7 DAYS
   STRUCTURAL SLAB — 10 DAYS
6. ALL REINFORCING STEEL, DOWEL, EMBEDDED HARDWARE, HOLD DOWN BOLTS, STRAPS, AND POST BASES MUST BE WELL SECURED IN PROPER LOCATIONS PRIOR TO PLACING CONCRETE.
7. MAXIMUM IN-PLACE DENSITY OF NONSTRUCTURAL LIGHTWEIGHT CONCRETE FLOOR TOPPING IS TO BE 100#/CU. FT.
8. REFER TO SLAB PLAN NOTES FOR ADDITIONAL INFORMATION, U.N.O.

REINFORCING STEEL:

1. ALL REINFORCING STEEL:
   NOTE: #5 AND SMALLER — ASTM A-615, GRADE 40
   #6 AND LARGER — ASTM A-615, GRADE 60
2. WELDED WIRE FABRIC — ASTM A-185
3. REINFORCING MARKED CONT. (CONTINUOUS) MAY BE SPLICED WITH LAPS AS SPECIFIED IN THE CODE, UNLESS OTHERWISE SPECIFIED.

SOILS AND FOUNDATION

1. THE FOUNDATION DESIGN IS BASED UPON THE SOILS REPORT BY
   THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL REQUIREMENTS THEREIN AND MAINTAIN A COPY ON THE JOBSITE AT ALL TIMES.
2. THE ENGINEER OF RECORD MUST BE INFORMED OF ANY CHANGES IN DESIGN CRITERIA MADE BY THE SOILS ENGINEER IN THE COURSE OF CONSTRUCTION.
3. ALL FOOTINGS AND SLABS SHALL BE FOUNDED ON FIRM UNDISTURBED NATURAL SOILS OR COMPACTED FILL. (PROVIDE BY SOILS ENGINEER)
4. ALL COMPACTED FILL SHALL BE PLACED IN AN APPROVED MANNER WITH A MINIMUM DENSITY OF 90% OF THE MAXIMUM OBTAINABLE IN ACCORDANCE WITH ASTM D 1557.
5. THE SOILS ENGINEER SHALL INSPECT AND APPROVE ALL FOUNDATION
6. SYSTEM AND ALL DRAINAGE SHALL BE CONDUCTED TO THE STREET IN AN ACCEPTABLE MANNER AND IN A NON-EROSIVE DEVICE.
7. REFER TO FOUNDATION PLANS, NOTES & DETAILS FOR ADDITIONAL INFORMATION.
8. ALLOWABLE SOIL BEARING PRESSURE: SEE NOTES ON PLAN

HARDWARE AND WOOD CONNECTORS

1. ALL WOOD FRAMING CONNECTORS SHALL BE SIMPSON "STRONG-TIE". INSTALLATION PROCEDURES SHALL BE IN ACCORDANCE WITH SIMPSON'S PRODUCT AND INSTRUCTION MANUAL/CATALOG C-2003.

   THE FOLLOWING ARE SPECIFIC REQUIREMENTS AND/OR CLARIFICATIONS TO THE SIMPSON MANUAL:

PA/MPA/HPA:	FASTENER	16d	COMMON
ST/MST:	FASTENER	16d	COMMON
PB/PC:	FASTENER	16d	COMMON
CB/CC:	FASTENER		MACHINE BOLT
HTT22	FASTENER	16d	SINKER
A35	FASTENER	8d	COMMON
NOTE: 8d x 1 1/2" MAY BE USED IF A35 IS NOT INSTALLED OVER SHEATHING.			
CMST	FASTENER	16d	COMMON
CS		8d	COMMON

SPECIAL INSPECTION:

THE SPECIAL INSPECTOR SHALL BE EMPLOYED BY THE OWNER, THE ENGINEER OR ARCHITECT OF RECORD, OR AN AGENT OF THE OWNER, BUT NOT THE CONTRACTOR OR ANY OTHER PERSON RESPONSIBLE FOR THE WORK.

THE FOLLOWING CONSTRUCTION PROCEDURES REQUIRE SPECIAL INSPECTION PER SECTION 1701 OF THE 2010 CBC:

- GLULAM BEAM

10. FOR LAG BOLTS: PROVIDE LEAD HOLES 65% TO 75% OF SHANK DIA. AND FULL DIA. FOR SHANK PORTION. SOAP, PARAFFINOR OR OTHER APPROVED LUBRICANT SHALL BE USED ON THREADS. INSTALLATION SHALL BE BY SCREWING, NO HAMMERING. CARE SHALL BE TAKEN TO AVOID OVER TORQUING OF THE BOLT.
11. ALL MUTI-STUDS ARE TO BE LAMINATED WITH 16d AT 12" O. C.
12. ALL BALLOON FRAMED WALLS SHALL BE BRACED TO CONFORM TO CBC 2007 TABLE 23-IV-B.
13. PROVIDE PREDRILLING WHERE NECESSARY TO AVOID SPLITTING.
14. ONLY COMMON NAILS SHALL BE USED FOR ALL WOOD SHEAR WALLS AND SHEAR TRANSFER CONNECTIONS. NAIL GUNS USING "CLIPPED HEADS" OR "SINKER" NAILS ARE NOT ACCEPTABLE.
15. PROVIDE MINIMUM OF 1/2" EDGE DISTANCE FOR ALL PLYWOOD BOUNDARY NAILING IN SHEAR WALLS, ALL PLYWOOD EDGES SHALL BE BLOCKED. MIN. WIDTH OF BLOCKING TO RECEIVE PLYWOOD NAILING MUST NOT BE LESS THAN THE THICKNESS OF BOUNDARY MEMBER AS SPECIFIED ON SHEAR WALL SCHEDULE.
16. OMIT SHEATHING B.N. UNDER CMST STRAP. INSTALL CMST OVER SHEATHING, U.N.O.
17. TOE NAILING SHALL NOT BE USED IN A SHEAR CONNECTION.
18. HOLDOWN ANCHORS MUST BE TIED IN PLACE PRIOR TO FOUND. INSPECTION
19. DIAPHGRAM SHEATHING NAILS OR OTHER APPROVED SHEATHING CONNECTORS SHALL BE DRIVEN SO THAT THEIR HEAD OR CROWN IS FLUSH WITH THE SURFACE OF THE SHEATHING.
20. CARRY ALL MULTIPLE STUDS OR POSTS FROM FLOOR ABOVE DOWN TO FLOOR OR BEAM BELOW. PROVIDE 4X SOLID BLOCKING AT FLOOR LEVEL TO TRANSFER LOAD FROM UPPER POST TO LOWER POST.
21. NO UTILITY LINE PENETRATION IS ALLOWED AT SHEAR WALLS.
22. SEE DETAIL 15/SD-5 FOR TYP. TOP PLATE SPLICE, UNO USE ST6224 AT ALL 2X4 TO 2X6 PLATE BREAKS.

GLUED LAMINATED LUMBER

1. STRUCTURAL GLUED LAMINATED LUMBERS SHALL BE FABRICATED BY A LOS ANGELES CITY BUILDING DEPARTMENT LICENSED SHOP AND IN ACCORDANCE WITH ANSI A190.1 AND APA-EWS117 OR AITC 117.
2. INDIVIDUAL LAMINATIONS SHALL NOT EXCEED 2 INCHES IN NET THICKNESS.
3. MOISTURE CONTENT SHALL BE FROM 7% TO 12%.
4. ALL GLU-LAMS SHALL BE DELIVERED TO JOBSITE WITH AITC CERTIFICATES. AITC CERTIFICATE SHALL BE PROVIDED TO THE BLDG. INSPECTOR PRIOR TO INSTALLATION.
5. PROVIDE TENSION LAMINATION AT BOTTOM OF BEAMS AND AT TOP OF CONTINUOUS BEAMS OVER COLUMNS, UNLESS NOTED OTHERWISE.
6. CAMBER - STANDARD, UNLESS NOTED ON PLANS.
7. LAMINATED BEAMS SHALL BE APA-EWS. DOUGLAS FIR GLULAMS & PROVIDE STRESS VALUES THAT MEET OR EXCEED THE REQUIREMENTS FOR EWS 24F-V4 DF/DF COMBINATION.

FLEXURAL STRESS	Fb = 2,400 PSI
TENSION PARALLEL TO GRAIN	Ft = 1,100 PSI
COMPRESSION PARALLEL TO GRAIN	Fc = 1,650 PSI
HORIZONTAL SHEAR PERPENDICULAR TO WIDE FACE	Fv = 240 PSI
MODULUS OF ELASTICITY	E = 1.8×10^6
COMPRESSION PERPENDICULAR TO GRAIN	
TENSION FACE	Fc = 650 PSI
COMPRESSION FACE	Fc = 650 PSI

7. ENDS OF BEAMS SHALL BE SEALED AND BEAMS SHALL BE WRAPPED FOR PROTECTION PRIOR TO CONSTRUCTION. HANDLING AND STORAGE OF GLB'S TO CONFORM TO AITC 111-79.
8. ALL GLB EXPOSED TO WEATHER OR MOISTURE SHALL BE FACTORY PRESSURE TREATED.

STEEL MOMENT FRAME NOTES

A. GENERAL

1. NOT USED
2. NOT USED
3. ALL COMPLETE-JOINT-PENETRATION GROOVE WELD USED IN THE SEISMIC FORCE RESISTING SYSTEM SHALL BE MADE WITH A FILLER METAL THAT HAS A MINIMUM CHARPY V-NORCH TOUGHNESS OF 20 FT-LBS AT MINUS 20°F. AISC I-7.3b
4. DISCONTINUITIES IN WELD CREATE BY ERRORS OR BY FABRICATION OR ERECTION OPERATIONS, SUCH AS TACK WELDS, ERECTION AIDS, AIR-ARC GOUGING AND FLAME CUTTING, SHALL BE REPAIRED AS REQUIRED BY THE ENGINEER OF RECORD.

B. ORDINARY MOMENT-RESISTING FRAMES (OMRF)

1. FOR CONNECTIONS WITH WELDED FLANGE JOINTS, WELD BACKING AND RUN-OFF TABS SHALL BE REMOVED AND REPAIRED INCLUDING THE USE OF A REINFORCING

   FILLET WELD, EXCEPT THAT THE TOP-FLANGE BACKING IS PERMITTED TO REMAIN IN PLACE IF IT IS ATTACHED TO THE COLUMN FLANGE WITH A CONTINOUS FILLET WELD ON THE EDGE BELOW THE COMPLETE-JOINT-PENETRATION GROOVE WELD.

ZONE 4 HARDWARE

1. ALL ZONE FOUR PRODUCT SHALL BE PER LARR #25334.
2. ALL ZONE FOUR PRODUCT SHALL BE INSTALLED ACCORDING TO THE ZONE FOUR PRODUCT AND INSTRUCTION MANUAL.

WELDED CONNECTION SPECIFICATIONS

1. NOT USED
2. COMPLETE JOINT PENETRATION GROOVE WELDS SHALL HAVE A FILLER METAL WITH A CHARPY V-NOTCH TOUGHNESS OF 20 FOOT-POUNDS AVERAGE AT MINUS TWENTY DEGREES FAHRENHEIT.
3. A WELDING PROCEDURE SPECIFICATION (W.P.S.) PER A.W.S. D1.1 SHALL BE DEVELOPED BY THE FABRICATOR/ERECTOR AND APPROVED BY THE ENGINEER OF RECORD OR HIS DESIGNEE. THE W.P.S. SHALL INCLUDE THE WELDING PARAMETERS RECOMMENDED BY THE ELECTRODE MANUFACTURER.
4. TO ASSURE THE PROPER AMPERAGE AND VOLTAGE OF THE WELDING PROCESS, THE USE OF A HAND HELD CALIBRATED AMP AND VOLT METER SHALL BE USED. THIS EQUIPMENT SHALL BE USED BY THE FABRICATOR, ERECTOR AND THE INSPECTORS. AMPERAGE AND VOLTAGE SHALL BE MEASURED NEAR THE ARC. TRAVEL SPEED AND ELECTRODE STICK OUT SHALL BE VERIFIED TO BE IN COMPLIANCE WITH THE APPROVED W.P.S.

FABRICATION PROCEDURES

1. NOT USED
2. WELDING SEQUENCE: BOTH FLANGES SHALL BE WELDED PRIOR TO ANY SUPPLEMENTAL WELDING TO THE SHEAR TAB.
3. AFTER WELDING, THE BACKING BAR AND THE RUN-OFF TABS ARE TO BE REMOVED FROM THE BOTTOM FLANGE. (NOTE, ONLY THE RUN-OFF TABS NEED TO BE REMOVED FROM THE TOP FLANGE, NOT THE BACKING BAR). THE WELD ROOT SHALL BE INSPECTED AND TESTED PER A.W.S. REQUIREMENTS GIVEN IN SECTION 8. IF REJECTABLE INDICATIONS ARE FOUND, REMOVE BY BACK GOUGING TO SOUND METAL. THE BACK GOUGED AREA SHALL BE WELDED AND IF REINFORCING PLATES ARE NOT USED, THE WELD SHALL BE REINFORCED WITH A FILLET WELD. THE SIZE OF THE REINFORCING FILLET WELD SHALL BE EQUAL TO 1/4 OF THE BEAM FLANGE THICKNESS, BUT NOT LESS THAN 1/4" AND NOT IN EXCESS OF 3/8" PER A.W.S. D1.1-94, NOTE J OF FIGURE 2.4.
4. FOR THE WELD OF THE BOTTOM BEAM FLANGE TO THE COLUMN FLANGE, FOLLOW STEPS A THROUGH G BELOW:

   A. THE ROOT PASS SHOULD NOT EXCEED 1/4" IN LAYER THICKNESS.

   B. THE FIRST HALF LENGTH ROOT SHOULD BE MADE WITH ONE OF THE FOLLOWING TECHNIQUES, AT THE OPTION OF THE CONTRACTOR:

   (1) THE ROOT PASS MAY BE INITIATED NEAR THE CENTER OF THE JOINT. IF THIS APPROACH IS USED, THE WELDER SHOULD EXTEND THE ELECTRODE THROUGH THE WELD ACCESS HOLE, APPROXIMATELY 1" BEYOND THE OPPOSITE SIDE OF THE GIRDER WEB. THIS IS TO ALLOW ADEQUATE ACCESS FOR CLEARING AND INSPECTION OF THE INITIATION POINT OF THE WELD BEFORE THE SECOND HALF-LENGTH OF THE ROOT PASS IS APPLIED. IT IS NOT DESIRABLE TO INITIATE THE ARC IN THE EXACT CENTER OF THE GIRDER WIDTH SINCE THIS WILL LIMIT ACCESS TO THE START OF THE WELD DURING POST-WELD OPERATIONS. AFTER THE ARC IS INITIATED, TRAVEL SHOULD PROGRESS TOWARD THE END OF THE JOINT (OUTBOARD BEAM FLANGE EDGE), AND THE WELD SHOULD BE TERMINATED ON A WELD TAB/RUN OFF TAB. TABS SHALL EXTEND THE JOINT, NO END DAMS.

   (2) THE WELD MAY BE INITIATED ON THE WELD TAB, WITH TRAVEL PROGRESSING TOWARD THE CENTER OF THE GIRDER FLANGE WIDTH. WHEN THIS APPROACH IS USED, THE WELDER SHOULD STOP WELD APPROXIMATELY 1" BEFORE THE BEAM WEB. IT IS NOT ADVISABLE TO LEAVE THE WELD CRATER DIRECTLY IN THE CENTER OF THE BEAM FLANGE WIDTH SINCE THIS WILL HINDER POST-WELD OPERATIONS.

   C. THE HALF LENGTH ROOT PASS THROUGH BE THOROUGHLY SLAGGED AND CLEANED.

   D. THE END OF THE HALF LENGTH ROOT PASS THAT IS NEAR THE CENTER OF THE BEAM FLANGE SHOULD BE VISUALLY INSPECTED TO ENSURE FUSION, SOUNDNESS, FREEDOM FROM SLAG INCLUSIONS AND EXCESSIVE POROSITY.

   THE RESULTING BEAD PROFILE SHOULD BE SUITABLE FOR OBTAINING FUSION BY THE SUBSEQUENT PASS TO BE INITIATED ON THE OPPOSITE SIDE OF THE GIRDER WEB. IF THE PROFILE IS NOT CONDUCIVE TO GOOD FUSION, THE START OF THE FIRST ROOT PASS SHOULD BE GROUND GOUGED, CHIPPED OR OTHERWISE PREPARED TO ENSURE ADEQUATE FUSION.

   E. THE SECOND HALF OF THE WELD JOINT SHOULD HAVE THE ROOT PASS APPLIED BEFORE ANY OTHER WELD PASSES ARE PERFORMED. THE ARC SHOULD BE INITIATED AT THE END OF THE HALF LENGTH ROOT PASS THAT IS NEAR THE CENTER OF THE BEAM FLANGE, AND TRAVEL SHOULD PROGRESS TO THE OUTBOARD END OF THE JOINT, TERMINATING ON THE WELD TAB.

   F. EACH WELD LAYER SHOULD BE COMPLETED ON BOTH SIDES OF THE JOINT BEFORE A NEW LAYER IS DEPOSITED.

   G. WELD TABS SHOULD BE REMOVED AND GROUND FLUSH TO THE BEAM FLANGE.

   DEVIATION FROM THE PRECEDING PROCEDURES MAY BE MADE PROVIDING THE CONTRACTOR SUBMITS IN WRITING AN ALTERNATE SEQUENCE THAT IS APPROVED BY THE ENGINEER PRIOR TO FABRICATION OR REPAIR.
5. FIELD WELDING OF REINFORCING STEEL SHALL BE PERFORMED BY WELDERS SPECIFICALLY CERTIFIED FOR REINFORCING STEEL. PRIOR TO WELDING, THE "CARBON EQUIVALENT" (CE) OF STEEL SHALL BE DETERMINED. REINFORCING STEEL WHOSE "CE" CANNOT BE IDENTIFIED OR WHOSE "CE" EXCEEDS 0.75% SHALL NOT BE WELDED. EXCEPT FOR REINFORCING STEEL CONFORMING ASTM A706, REINFORCING STEEL SHALL BE PREHEATED AS SHOWN IN TABLE LRGA 3-77. IN ADDITION, STEEL WITH "CE" BETWEEN 0.66% AND 0.75% SHALL BE WELDED ONLY
6. DISCONTINUITIES IN WELD CREATED BY ERRORS OR BY FABRICATION OR ERECTION OPERATIONS; SUCH AS TACK WELDS, ERECTION AIDS, AIR-ARC GOUGING, AND FLAME CUTTING; SHALL BE REPAIRED AS REQUIRED BY THE ENGINEER OF RECORD.
7. THE SEISMIC DESIGN, FABRICATION, AND ERECTION OF STRUCTURAL STEEL SHALL BE IN ACCORDANCE WITH PART I (LRFD) AND PART III (ASD) OF THE SEISMIC PROVISIONS FOR STRUCTURAL STEEL BUILDINGS, APRIL 15, 1997, PUBLISHED BY AISC. THESE PROVISIONS SHALL BE APPLIED IN CONJUNCTION WITH CHAPTER 22, DIVISION II.

NAIL DEFINITIONS

DESIGNATION	DIA.	LENGTH
16d COMMON	0.162	3 1/2"
16d SINKER	0.148	3 1/4"
16d SHORT	0.131	3 1/4"
8d COMMON	0.131	2 1/2"
10d COMMON	0.148	3"

WOOD

1. ALL LUMBER USED FOR STRUCTURAL PURPOSES SHALL BE DOUGLAS FIR LARCH, COAST REGION, GRADED IN ACCORDANCE WITH THE WEST COAST LUMBER INSPECTION BUREAU. ALL LUMBER SHALL BE LESS THAN 19% MOISTURE CONTENT FOR ALL CONSTRUCTION. CONTRACTOR SHALL TEST AND MANAGE MOISTURE CONTENT TO ENSURE PROPER MOISTURE CONTENT DURING ALL STORAGE AND HANDLING OPERATIONS.
2. THE MINIMUM GRADES SHALL BE AS FOLLOWS UNLESS NOTED OTHERWISE ON PLANS (ALL WOOD MUST BE GRADE MARKED):

HORIZONTAL FRAMING MEMBERS (JOIST AND BEAMS)	
2X	D.F. #2
4X12 OR SMALLER	D.F. #2
4X14 OR LARGER	D.F. #1
6X	D.F. #1
8X	D.F. #1
VERTICAL FRAMING MEMBERS (STUD AND POST)	
2X4	STANDARD OR STUD GRADE
3X4	D.F. #2
2X6	D.F. #2
4X4, 4X6	D.F. #2
6X6 OR LARGER	D.F. #1
MISCELLANEOUS	
SILL PLATE (GROUND FLOOR)	P.T. D.F. #2
SOLE PL. (UPPER FLOORS)	D.F. #2
2X TOP PLATE	D.F. #2
SHEAR BLOCKING	D.F. #2
NON-STRUCTURAL BLOCKING & BRIDGING	UTILITY

3. ALL BLOCKING SHALL BE CUT TO FIT FLUSH AGAINST SHEATHING AND OTHER OTHER FRAMING MEMBER.
4. ALL SILL PLATES BEARING ON MASONRY OR CONCRETE FOUNDATION WALL OR SLAB ON GRADE SHALL BE PRESSURE TREATED IN ACCORDANCE WITH CBC 2303.3.1 SILL PLATES SHALL BE BOLTED TO THE FOUNDATION WITH 5/8 INCH DIAMETER BOLTS AT 4'-0" ON-CENTER MAXIMUM. U.N.O. ON SHEAR WAL SCHED. EMBEDDED 7 INCH MINIMUM IN CONCRETE. BOLTS SHALL HAVE PLATE WASHERS 3"x3"X1/4" . MINIMUM 2 BOLTS PER PLATE. ONE BOLT WITHIN 12 INCHES BUT NO LESS THAN 7 BOLT DIAMETERS, OF PLATE END AND CORNERS.
5. WALL FRAMING TO BE 2X STUDS AT 16 INCHES ON-CENTER ON EXTERIOR WALLS AND 2X STUDS AT 16 INCHES ON-CENTER AT INTERIOR WALLS, U.N.O. PROVIDE DOUBLE TOP PLATE ON ALL WALLS WITH MINIMUM 48 INCH LAP SPLICE. UNLESS SPECIFICALLY NOTED ON PLANS, THE MAXIMUM STUD HEIGHT FOR 2X4 EXTERIOR WALL IS 10 FEET. FOR 2X4 INTERIOR WALL IS 14 FEET. MAXIMUM NON-BEARING STUD HEIGHT FOR 2X6 STUDS IS 20 FEET, U.N.O.
6. PROVIDE 0.058" X 1-1/2" WIDE STEEL TIE STRAPS WITH 6-16d NAILS AT EACH SIDE WHERE PLATES ARE INTERRUPTED BY UTILITY PENETRATIONS @ NON-SHEARWALLS. IF PENETRATIONS WILL OCCUR @ SHEAR WALL, NOTIFY THE ENGINEER PRIOR TO STARTING WORK.
7. PROVIDE 1X6 LET-IN DIAGONAL BRACES AT EACH 25 LINEAR FEET OF NON-SHEAR WALL EACH CORNER, AND ALL MAIN CROSS STUD PARTITIONS. LET-IN TO CROSS 4 STUD SPACES AT 45 DEGREES WHERE POSSIBLE. SOLID BLOCKING SHALL BE PROVIDED AT ALL HORIZONTAL JOINTS OCCURING IN BRACED WALLS.
8. PROVIDE SINGLE JOISTS UNDER NON-BEARING PARTITION PARALLEL TO JOISTS. PROVIDE MINIMUM 2 FLOOR JOISTS BELOW BEARING WALLS UNLESS NOTED OTHERWISE ON PLANS.
9. ROOF SHEATHING SHALL BE INSPECTED PRIOR TO PLACING INSULATION AND ROOFING.
10. ALL RATED SHEATHING SHALL BE IDENTIFIED WITH THE GRADE TRADEMARK OF APA- THE ENGINEERED WOOD ASSOCIATION AND SHALL MEET THE REQUIREMENTS OF PRODUCTS STANDARD APA PRP 108. ALL APA RATED SHEATHING WHICH HAS ANY EDGE OR SURFACE PERMANENTLY EXPOSED TO THE WEATHER SHALL BE OF THE EXTERIOR TYPE. APA RATED SHEATHING SHEET LESS THAN 24 INCHES IN ANY DIMENSION SHALL NOT BE USED IN SHEAR WALLS, FLOOR, OR ROOF DIAPHRAGM.

    ROOF SHEATHING: 15/32 INCH A.P.A. RATED SHEATHING, EXP. 1, 32 / 16 WITH 8D COMMON AT 6 INCHES ON-CENTER AT PANEL EDGES, AND 12 INCHES ON-CENTER AT INTERMEDIATE SUPPORT, PI (24/0). LAY PANEL WITH FACE GRAIN OR STRENGTH AXIS PERPENDICULAR TO SUPPORTS AND WITH PANEL CONTINUOUS OVER TWO OR MORE SPANS.

    FLOOR SHEATHING: 23/32 INCH A.P.A. RATED STURD-I-FLOOR, EXP 1, T&G, 24" OC WITH 10d COMMON (OR 10d RING SHANK/SCREW SHANK) AT 6 INCHES ON-CENTER AT EDGES AND 12 INCHES ON-CENTER AT INTERMEDIATE SUPPORT, P.I. (48/24 LAY PANEL WITH FACE GRAIN OR STRENGTH AXIS PERPENDICULAR TO SUPPORTS, AND WITH PANEL CONTINUOUS OVER TWO OR MORE SPANS.

    DECK SHEATHING: DO NOT USE OSB UNLESS APPROVED BY ARCH.

    SHEAR PANEL: A.P.A. RATED STRUCT. I SHEATHING
11. FLOOR JOIST ARE NOT DESIGNED TO SUPPORT WATER BEDS. ENGINEER OF RECORD TO BE NOTIFIED IF WATER BEDS ARE TO BE USED.
12. STRUCTURAL MEMBERS SHALL NOT BE CUT OR NOTCHED UNLESS SPECIFICALLY DETAILED BY THE ENGINEER OF RECORD.
13. FRAMING FOR PRE-FABRICATED FIREPLACE FLUES SHALL BE BALLOON FRAMED FULL HEIGHT USING 2x4 STUDS AT 16" O.C. BRACED AT MID-HEIGHT AND AT THE PLATE HEIGHTS. U.N.O. ON PLAN MAXIMUM UNBRACED LENGTH IS 14'.
14. ALL BEAMS TO BE SUPPORTED WITH FULL BEARING MULTISTUD OR POST, U.N.O.
15. CARRY ALL MULTIPLE STUDS OR POSTS FROM FLOOR ABOVE DOWN TO FLOOR OR BEAM BELOW. PROVIDE 4X SOLID BLOCKING AT FLOOR LEVEL TO TRANSFER LOAD FROM UPPER POST TO LOWER POST.
16. INTERIOR NON-BEARING HEADERS MAY BE 2X4 FLAT. INSTALL 4X4 AT 6' AND 8'

GENERAL

ALL WORK TO CONFORM TO THE 2008 LABC AND 2019 CRC AS AMENDED BY THE CITY OF SAN DIEGO, CA.

1. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS, CONDITIONS AT THE JOBSITE, AND TO CROSS CHECK ALL DETAILS AND DIMENSIONS SHOWN ON THE STRUCTURAL DRAWINGS WITH RELATED REQUIREMENTS ON THE ARCHITECTURAL, MECHANICAL, ELECTRICAL, AND/OR CIVIL DRAWINGS AND NOTIFY THE ARCHITECT AND ENGINEER OF ANY DISCREPANCIES PRIOR TO STARTING WORK.
2. FLOOR AND WALL OPENINGS, SLEEVES, VARIATIONS IN STRUCTURAL SLAB ELEVATIONS, DEPRESSED AREAS AND ALL OTHER ARCHITECTURAL, MECHANICAL, ELECTRICAL, AND/OR CIVIL REQUIREMENTS MUST BE COORDINATED BEFORE THE CONTRACTOR PROCEEDS WITH CONSTRUCTION.
3. IN ALL CASES WHERE A CONFLICT MAY OCCUR SUCH AS BETWEEN ITEMS INCLUDED IN THE SPECIFICATIONS AND NOTES ON THE DRAWINGS OR BETWEEN GENERAL NOTES AND SPECIFIC DETAILS, THE ENGINEER SHALL BE NOTIFIED AND WILL INTERPRET THE INTENT OF THE CONTRACT DOCUMENT.
4. DETAIL MARKED "TYPICAL" SHALL APPLY IN ALL CASES UNLESS SPECIFICALLY INDICATED OTHERWISE.
5. WHERE NO SPECIFIC DETAIL IS SHOWN, THE FRAMING OR CONSTRUCTION SHALL BE IDENTICAL OR SIMILAR TO THAT INDICATED FOR LIKE CASES OF CONSTRUCTION.
6. EXCEPT WHERE MORE STRINGENT REQUIREMENTS ARE NOTED OR SHOWN IN THE PLANS OR SPECIFICATIONS, ALL PHASES OF WORKMANSHIP AND MATERIALS SHALL CONFORM TO THE REQUIREMENTS OF THE UNIFORM BUILDING CODE, LATEST EDITION, AS WELL AS ALL APPLICABLE STATE AND LOCAL ORDINANCES.
7. IN NO CASE SHALL WORKING DIMENSIONS BE SCALED FROM PLANS, SECTIONS, OR DETAILS ON THE STRUCTURAL DRAWINGS.
8. THE PRECISE DIMENSIONS AND LOCATIONS OF ALL DOOR AND WINDOW OPENINGS SHALL BE DETERMINED FROM THE ARCHITECTURAL DRAWINGS; OTHER FLOOR, WALL AND ROOF OPENINGS AS REQUIRED BY MECHANICAL ELECTRICAL OR SIMILAR REQUIREMENTS SHALL BE VERIFIED FROM SHOP DRAWINGS, EQUIPMENT DATA, ETC., AS REQUIRED.
9. THE CONSTRUCTION DOCUMENT REPRESENTS A FINISHED PRODUCT. UNLESS NOTED OTHERWISE, IT DOES NOT INDICATE THE METHOD OF CONSTRUCTION. TEMPORARY BRACING, SHORING AND TEMPORARY SUPPORT FOR ANY STRUCTURAL COMPONENTS AND FOR CONSTRUCTION LOAD IMPOSED BY CONSTRUCTION EQUIPMENT AND / OR ARISEN DUE TO THE WEIGHT OF THE STORED CONTRUCTION MATERIALS. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR THE CONSTRUCTION MEANS, METHODS AND PROCEDURES.
10. VIBRATIONAL ANALYSIS OF ANY MECHANICAL EQUIPMENT HAS NOT BEEN CONSIDERED BY ENGINEER OF RECORD.
11. IN OTHER THAN POST-TENTIONED CONSTRUCTION, THE SLAB-ON-GRADE IS CONSIDERED A NON-STRUCTURAL COMPONENT AND IS THEREFORE NOT DESIGNED BY THE ENGINEER, EXCEPT FOR THOSE PORTIONS OF THE SLAB -ON-GRADE OCCURRING DIRECTLY ABOVE A FOOTING.
12. CONTRACTOR TO ENSURE THAT ALL DRAINAGE IS DIRECTED AWAY FROM THE EXTERIOR FOOTINGS (MIN. 2 % SLOPE). REFER TO SOIL REPORT FOR ADDITIONAL RECOMMENDATIONS.
13. THE USE OF THESE PLANS, DRAWINGS, SPECIFICATIONS, AND/OR ELEVATIONS IS RESTRICTED TO THE ORIGINAL USE FOR WHICH THEY WERE PREPARED AND FURNISHED TO THE HOLDER. PUBLICATION THEREOF IS EXPRESSLY LIMITED TO SUCH USE. REUSE, REPRODUCTION OR OTHER PUBLICATION BY ANY METHOD IS PROHIBITED AND MAY RESULT IN LIABILITY FOR DAMAGES. VANDORPE CHOU ASSOCIATES, INC. ASSUMES NO LIABILTY FOR THE UNAUTH-ORIZED USE OF THESE PLANS.
14. THESE PLANS AND SPECIFICATIONS ARE TO SHOW THE PRIMARY STUCTURAL SYSTEM AND ARE SOLELY FOR THE USE OF A BUILDER KNOWLEDGEABLE AND EXPERIENCED IN THIS TYPE OF WORK. STRUCTURAL COMPONENTS WHICH ARE NOT A PART OF THE PRIMARY STRUCTURAL SYSTEM: SUCH AS GLAZING WINDOW WALLS, GUARDRAILS, TEMPORARY SHORING, MANUFACTURED STRUCTURAL ELEMENTS, SITE IMPROVEMENTS, PAVING, DRAINAGE STRUCTURES, FREE STANDING SIGNS AND POLES, AND LANDSCAPE IMPROVEMENTS ARE NOT A PART OF THIS WORK.
15. ALL WORK OF THE CONTRACTOR, SUB-CONTACTORS, AND BUILDER SHALL CONFORM TO CURRENT GOOD PRACTICES. NOT ALL ASPECTS OF GOOD PRACTICES ARE SHOWN ON THE CONTRACT DRAWINGS.
16. DURING THE COURSE OF CONSTRUCTION CHANGES MAY OCCUR, THEREFORE THE ENGINEER OF RECORD MAKES NO REPRESENTATIONS REGARDING THE ACCURACY OF THESE PLANS TO THE "AS-BUILT" PRODUCT.
17. COORDINATE WITH ARCHITECTURAL DRAWINGS FOR LOCATION AND CONSTRUCTION OF DRAFTSTOPS, FIRE BLOCKING, DAMPERS AND OTHERS ITEMS NECESSARY FOR FIRE PROTECTION. COORDINATE WITH ARCHITECTURAL DRAWINGS FOR LOCATION AND CONSTRUCTION OF FLASHING, BLOCKING, EXTERIOR FINISHES, TREATMENTS OR OTHER MATERIAL REQUIRED FOR DAMPPROOFING OR MOISTURE CONTROL.
18. FOR ANY PRE-MANUFACTURED PRODUCTS OR MATERIALS OF CONSTRUCTION, CONTRACTOR SHALL BE RESPONSIBLE FOR BEING FAMILIAR WITH AND FOR PROPER EXECUTION OF MANUFACTURER'S INSTRUCTIONS, REQUIREMENTS AND CONDITIONS OF APPROVAL PRIOR TO INSTALLATION AND/OR USE.
19. SOME STRUCTURAL COMPONENTS ARE REQUIRED BY CODE TO BE PROTECTED FROM WATER/MOISTURE PENETRATION OR FROM FIRE DAMAGE. THE METHODS OF PROTECTION OF THESE STRUCTURAL COMPONENTS ARE NOT THE RESPONSIBILITY OF THE ENGINEER OF RECORD AND NOT DETAILED. REFER TO THE ARCHITECTURAL DOCUMENTS AND THE BUILDING CODE FOR WATER / MOISTURE PROOFING METHODS AND FIRE PROOFING DETAILS.
20. THERE SHALL BE NO TRENCHES OR EXCAVATIONS 5 FEET OR MORE IN DEPTH INTO WHICH A PERSON IS REQUIRED TO DESCEND OR OBTAIN NECESSARY PERMIT FROM STATE OF CALIFORNIA, DIVISION OF INDUSTRIAL SAFETY PRIOR TO THE ISSUANCE OF A BUILDING OR GRADING PERMIT.
21. ANY ASTM DESIGNATIONS SHALL BE AS AMENDED TO DATE.

RESIDENTIAL NAILING SCHEDULE

TABLE R602.3(1) FASTENER SCHEDULE FOR STRUCTURAL MEMBERS

ITEM	DESCRIPTION OF BUILDING ELEMENTS	NUMBER AND TYPE OF FASTENERS a, b, c	SPACING OF FASTENERS
Roof			
1	Blocking between joists or rafters to top plate, toe nail	4-8d box (2 1/2" x 0.113") or 3-8d (2 1/2" x 0.113"); or 3-10d box (3"x0.128"); or 3-3"x0.131" nails	Toe nail
2	Ceiling joists to plate, toe nail	4-8d box (2 1/2" x 0.113") or 3-8d (2 1/2" x 0.113"); or 3-10d box (3"x0.128"); or 3-3"x0.131" nails	Per joist, toe nail
3	Ceiling joists not attached to parallel rafter, laps over partitions, face (see Sections R802.3.2, R802.3.2 and Table R802.5.1(9))	4-10d box (3"x0.128"); or 3-16d common (3 1/2" x 0.162"); or 4-3"x0.131" nails	Face nail
4	Ceiling joist attached to parallel rafter (heel joint) (see Sections R802.3.1 and R802.3.2 and Table R802.5.1(9))	Table R802.5.1(9)	Face nail
5	Collar tie to rafter, face nail or 1 1/4" x 20 gage ridge strap to rafter	4-10d box (3"x0.128"); or 3-10d common (3" x 0.148"); or 4-3"x0.131 nails	Face nail each rafter
6	Rafter or roof truss to plate	3-16d box nails (3 1/2" x 0.135"); or 3-10d common nails (3" x 0.148"); or 4-10d box (3"x0.128"); or 4-3"x0.131" nails	2 toe nails on one side and 1 toe nail on opposite side of each rafter or truss
7	Roof rafters to ridge, valley or hip rafters or roof rafter to minimum 2" ridge beam	4-16d box (3 1/2" x 0.135"); or 3-10d common (3" x 0.148"); or 4-10d box (3"x0.128"); or 4-3" x 0.131 nails	Toe nail
		3-16d box (3 1/2" x 0.135"); or 3-16d common (3 1/2" x 0.148"); or 3-10d box (3"x0.128"); or 3-3" x 0.131 nails	End nails
Wall			
8	Stud to stud (not at braced wall panels)	16d common (3 1/2" x 0.162")	24" o.c. face nail
		10d box (3" x 0.128"); or 3"x0.131" nails	16" o.c. face nail
9	Stud to stud and abutting studs at intersecting wall corners (at braced wall panels)	16d box (3 1/2" x 0.135"); or 3" x 0.131" nails	12" o.c.
		16d common (3 1/2" x 0.162")	16" o.c. face nail
10	Built-up header (2" to 2" header with 1/2" spacer)	16d common (3 1/2" x 0.162")	16" o.c. each edge face nail
		16d box (3 1/2" x 0.135")	12" o.c. each edge face nail
11	Continuous header to stud	5-8d box (2 1/2" x 0.113"); or 4-8d common (2 1/2" x 0.131"); or 4-10d box (3" x 0.128")	Toe nail
12	Top plate to top plate	16d common (3 1/2" x 0.162")	16" o.c. face nail
		10d box (3" x 0.128"); or 3" x 0.131" nails	12" o.c. face nail
13	Double top plate splice	8-16d common (3 1/2" x 0.162"); or 12-16d box (3 1/2" x 0.135"); or 12-10d box (3" x 0.128"); or 12-3" x 0.131 nails	Face nail on each side of end joint (minimum 24" lap splice length each side of end joint)
14	Bottom plate to joist, rim joist, band joist or blocking (not at braced wall panels)	16d common (3 1/2" x 0.162")	16" o.c. face nail
		16d box (3 1/2" x 0.135"); or 3" x 0.131" nails	12" o.c. face nail

ITEM	DESCRIPTION OF BUILDING ELEMENTS	NUMBER AND TYPE OF FASTENERS a, b, c	SPACING OF FASTENERS
15	Bottom plate to joist, rim joist, band joist or blocking (at braced wall panels)	3-16d box (3 1/2" x 0.135"); or 2-16d common (3 1/2" x 0.162"); or 4-3" x 0.131 nails	3 each 16" o.c. face nail; 2 each 16" o.c. face nail; 4 each 16" o.c. face nail
16	Top or bottom plate to stud	4-8d box (2 1/2" x 0.113"); or 3-16d box (3 1/2" x 0.135"); or 4-8d common (2 1/2" x 0.131"); or 4-10d box (3" x 0.128"); or 4-3" x 0.131 nails	Toe nail
		3-16d box (3 1/2" x 0.135"); or 2-16d common (3 1/2" x 0.162"); or 3-10d box (3" x 0.128"); or 3-3" x 0.131 nails	End nail
17	Top plates, laps at corners and intersections	3-10d box (3" x 0.128"); or 2-16d common (3 1/2" x 0.162"); or 3-3" x 0.131 nails	Face nail
18	1" brace to each stud and plate	3-8d box (2 1/2" x 0.113"); or 2-8d common (2 1/2" x 0.131"); or 2-10d box (3" x 0.128"); or 2 staples 1 3/4"	Face nail
19	1" x 6" sheathing to each bearing	3-8d box (2 1/2" x 0.113"); or 2-8d common (2 1/2" x 0.131"); or 2-10d box (3" x 0.128"); or 2 staples, 1" crown, 16 ga., 1 3/4" long	Face nail
20	1" x 8" and wider sheathing to each bearing	3-8d box (2 1/2" x 0.113"); or 3-8d common (2 1/2" x 0.131"); or 3-10d box (3" x 0.128"); or 3 staples 1" crown, 16 ga., 1 3/4" long; Wider than 1" x 8": 4-8d box (2 1/2" x 0.113"); or 3-8d common (2 1/2" x 0.131"); or 3-10d common (3" x 0.128"); or 4 staples, 1" crown, 16 ga., 1 3/4" long	Face nail
Floor			
21	Joist to sill, top plate or girder	4-8d box (2 1/2" x 0.113"); or 3-8d common (2 1/2" x 0.131"); or 3-10d box (3" x 0.128"); or 3-3" x 0.131" nails	Toe nail
22	Rim joist, band joist or blocking to sill or top plate (roof application also)	8d box (2 1/2" x 0.113")	4" o.c. toe nail
		8d common (2 1/2" x 0.131"); or 10d box (3" x 0.128"); or 3" x 0.131" nails	6" o.c. toe nail
23	1" x 6" subfloor or less to each joist	3-8d box (2 1/2" x 0.113"); or 2-8d common (2 1/2" x 0.131"); or 3-10d box (3" x 0.128"); or 2 staples, 1" crown, 16 ga., 1 3/4" long	Face nail
24	2" subfloor to joist or girder	3-16d box (3 1/2" x 0.135"); or 2-16d common (3 1/2" x 0.162")	Blind or face nail
25	2" planks (plank & beam - floor & roof)	3-16d box (3 1/2" x 0.135"); or 2-16d common (3 1/2" x 0.162")	At each bearing
26	Band or rim joist to joist	3-16d common (3 1/2" x 0.162"); 4-10 box (3" x 0.128"), or 4-3" x 0.131" nails, or 4-3" x 14 ga. staples, 7/16" crown	End nail
27	Built-up girders and beams, 2-inch lumber layers	20d common (4" x 0.192"); or	Nail each layer as follows: 32" o.c. at top and bottom and staggered
		10d box (3" x 0.128"); or 3" x 0.131" nails	24" o.c. face nail at top and bottom staggered on opposite sides
		And: 2-20d common (4" x 0.192"); or 3-10d box (3 1/2" x 0.128"); or 3-3" x 0.131" nails	Face nail at ends and at each splice
28	Ledger strip supporting joists or rafters	4-16d box (3 1/2" x 0.135"); or 3-16d common (3 1/2" x 0.162"); or 4-10d box (3" x 0.128"); or 4-3" x 0.131 nails	At each joist or rafter, face nail
29	Bridging to joist	2-10d (3" x 0.128"); or 2-8d common (2 1/2" x 0.131"); or 2- 3" x 0.131") nails	Each end, toe nail
ITEM	DESCRIPTION OF BUILDING	DESCRIPTION OF FASTENERS, c, a	SPACING OF FASTENERS

	MATERIALS		Edges (inches)	Intermediate supports c, e (inches)
Wood structural panels, subfloor, roof and interior wall sheathing to framing and particleboard wall sheathing to framing (see Table R602.3(3) for wood structural panel exterior wall sheathing to wall framing)				
30	3/8" - 1/2"	6d common (2" x 0.113") nail (subfloor wall); 8d common (2 1/2" x 0.131") nail (roof); or RSRS-01 (2 3/8" x 0.113" nail (roof) j	6	12f
31	19/32" - 1"	8d common nail (2 1/2" x 0.131"); or RSRS-01; (2 3/8" x 0.113") nail (roof)	6	12f
32	1 1/8" - 1 1/4"	10d common (3" x 0.148") nail or 8d (2 1/2" x 0.131") deformed nail	6	12
Other wall sheathing h				
33	1/2" structural cellulosic fiberboard sheathing	1 1/2" galvanized roofing nail, 7/16" head diameter or 1 1/4" long 16 ga. Staple with 7/16" or 1" crown	3	6
34	25/32" structural cellulosic fiberboard sheathing	1 3/4" galvanized roofing nail, 7/16" head diameter or 1 1/2" long 16 ga. Staple with 7/16" or 1" crown	3	6
35	1/2" gypsum sheathing d	1 1/2" galvanized roofing nail; staple galvanized, 1 1/2" long; 1 1/4 screws, Type W or S	7	7
36	5/8" gypsum sheathing d	1 3/4" galvanized roofing nail; staple galvanized, 1 5/8" long; 1 5/8" screws, Type W or S	7	7
Wood structural panels, combination subfloor underlayment to framing				
37	3/4" and less	6d deformed (2" x 0.120") nail or 8d common (2 1/2" x 0.131") nail	6	12
38	7/8" - 1"	8d common (2 1/2" x 0.131") nail or 8d deformed (2 1/2" x 0.120") nail	6	12
39	1 1/8" - 1 1/4"	10d common (3" x 0.148") nail or 8d deformed (2 1/2" x 0.120") nail	6	12

For SI: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1 mile per hour = 0.447 m/s; 1 Ksi = 6.895 MPa.

a. Nails are smooth-common, box or deformed shanks except where otherwise stated. Nails used for framing and sheathing connections shall have minimum average bending yield strengths as shown: 80 ksi for shank diameter of 0.192 inch (20d common nail), 90 ksi for shank diameters larger than 0.142 inch but not larger than 0.177 inch, and 100 ksi for shank diameters of 0.142 inch or less.

b. Staples are 16 gage wire and have a minimum 7/16-inch on diameter crown width.

c. Nails shall be spaced at not more than 6 inches on center at all supports where spans are 48 inches or greater.

d. Four-foot by 8-foot or 4-foot by 9-foot panels shall be applied vertically.

e. Spacing of fasteners not included in this table shall be based on Table R602.3(2).

f. Where the ultimate design wind speed is 130 mph or less, nails for wood structural panel roof sheathing to gable end wall framing shall be spaced 6 inches on center. Where the ultimate wind speed is greater than 130 mph, nails for attaching panel roof sheathing to intermediate supports shall be spaced 6 inches on center for minimum 48-inch distance from ridges, eaves and gable end walls; and 4 inches on center to gable end wall framing.

g. Gypsum sheathing shall conform to ASTM C 1396 and shall be installed in accordance with GA 253. Fiberboard sheathing shall conform to ASTM C 208.

h. Spacing of fasteners on floor sheathing panel edges applies to panel edges supported by framing members and required blocking and at floor perimeters only. Spacing of fasteners on roof sheathing panel edges applies to panel edges supported by framing members and required blocking. Blocking of roof and floor sheathing panel edges perpendicular to the framing members need not be provided except as required by other provisions of this code. Floor perimeter shall be supported by framing members or solid blocking.

i. Where a rafter is fastened to an adjacent parallel ceiling joist in accordance with this schedule, provide two toe nails on one side of the rafter and toe nails from the ceiling joist to top plate in accordance with this schedule. The toe nail on the opposite side of the rafter shall not be required.

j. RSRS-01 is a Roof Sheathing Ring Shank nail meeting the specifications in ASTM F1667.

The fastener schedule provides minimum nailing requirements (i.e. size, spacing) for connecting building elements used in wood framed construction. For wood structural panels, both edge nailing and intermediate (field) nailing are specified. In addition to the nailing for wood structural panels, fasteners are specified for gypsum wall sheathing, cellulosic fiberboard wall sheathing and combination subfloor underlayment.

PLANNING
DESIGN
ENGINEERING

DELTA DESIGN Studio

9855 BLACK MT. RD I SAN DIEGO, CA 92126 I P (858)-335-0818 I F (800)-309-1008

4439 Keeler Ave ADU

4439 Keeler Ave.
San Diego, CA 92113

REGISTERED PROFESSIONAL ENGINEER HUY THIEU NGUYEN No. C62628 Exp. 06/30/2024 CIVIL STATE OF CALIFORNIA

Huy Nguyen

Revision Dates	
1	08.15.24
2	01.01.25

SHEET TITLE
Structure Notes

Drawing Date: 08.24.26

Check By: -

Drawn By: Author

Scale

Job Number: 081623

Sheet Number: SD0

8/27/2026 1:48:29 PM